

Appendix G - 2018/19 Cluster Site Monitoring.

Location	Measures	Progress	Annual Collisions (Before)	Annual Collisions (After) ¹
A426 Lutterworth Road Whetstone j/w Countesthorpe Road	Signing Lining	Completed	1.6	1
Quorn, C5214 Loughborough Road j/w Farley Way	Signing Signal changes	Completed	1.4	0
B4114 St Johns j/w B582 Blaby Road Foxhunter Roundabout	Traffic signals	Completed	2.0	0
C3208 Shepshed Road Ulverscroft j/w Beacon Road	Signing Lining	Completed	1.6	3
Blaby by pass/Whetstone Roundabout	Signing Visirail	Completed	2.6	1
Charley, B591 Loughborough Road j/w Charley Road	Signing Resurfacing	Completed	1.4	2
Burbage, B4109 Rugby Road j/w Sketchley Road	Lining	Completed	1.4	0
Bitteswell, A426 Leicester Road j/w Ullesthorpe Road	VAS Signing Lining	Awaiting completion (VAS)	1.4	N/A
Dunton Bassett, A426 Lutterworth Road j/w Coopers Lane	Signing Lining	Completed	1.2	0
A47 Uppingham Road/B6047	Signing VAS	Awaiting completion (VAS)	2.6	N/A
Aston Flamville, B4669 Hinckley Road approx. 30m E of Smithy Lane	VAS Lining	Completed	1.6	0
A426 Leicester Road Glen Parva j/w Little Glen Road	Speed limit changes Signing	Completed	1.6	0
A6 Harborough Road, Market Harborough j/w Kettering Road	VAS changes	Completed	2.4	1
A512 Ashby Road / B5324 Rempstone Road	Lining/Signing	Completed	1.4	0
A563 Ashby Road JW The Green, Castle Donington	Lining/Signing	Completed	1.4	0
Charley Road/Iveshead Road/Abbey Road	VAS Lining Signing Road surfacing	Completed	4.6	N/A

¹ Annual collision 'after' data only provided for sites where 12 months data was available at the time of reporting.

This page is intentionally left blank